BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 14

Name of Work:-Development works at kempegowda statue premises in Kempegowda ward no-01 of Yelahanka Sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri JAGADISH (VARUN KARTHICK CONSTRUCTIONS)	
				Rate	Rate in Words
1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone	Cum	67.80	334.40	Three Hundred ThirtyFour Paise Fourty Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates.	Cum	15.45	6109.40	Six Thousand One Hundred Nine Paise Fourty Only
3	Providing Size Stone Masonty With hard Stone in Foundation & Plinth with Cement Mortor 1:6 .	Cum	30.78	5964.20	Five Thousand Nine Hundred SixtyFour Paise Twenty Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

Scanned with CamScanner

	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	8.42	6300.80	Six Thousand Three Hundred Paise Eighty Only
5	Fabricating, providing and erecting in position Hot dip galvanised Sq.Poles of 132 X 132 Heavy gauge of length 3000mm with MS Hot Dip Galvanised Grill work as per approved design and drawing of chief architect. Using 12 X 75mm Galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150 mm C/c as shown in drawing including providing forged ornamnetal arrow head at top and Bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. THe rate is inclusive of all materials like MS Hallow Galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery and incidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work	Sqm	84.30	14606.72	Fourteen Thousand Six Hundred Six Paise SeventyTwo Only
6	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineer-in-charge of the work	Sqm	11.75	20036.97	Twenty Thousand ThirtySix Paise NinetySeven Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara

Scanned with CamScanner

	Providing and fixing of wall cladding using 20mm thick gang saw water cut shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25 mm X 12 mm groves in joints including cost of all materials, mortor, labour, curing etc complete	Sqm	65.00	3380.30	Three Thousand Three Hundred Eighty Paise Thirty Only
8	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete as directed by the Engineer In Charge of the work	Nos	111.00	507.00	Five Hundred Seven Only
9	Painting Two Coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete Surfaces	Sqm	17.50	93.50	NinetyThree Paise Fifty Only
10	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	T.Km	86.78	198.00	One Hundred NinetyEight Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Scanned with CamScanner